

SECTION 5A

TRAFFIC CONTROL

5A.1 GENERAL

This section consists of furnishing all labor, materials, equipment and performing all operations in connections with performing traffic control plans in accordance with the SCDOT Encroachment Permit. The Permit is attached as the general conditions of the contract documents.

5A.2 WORK ZONE TRAFFIC CONTROL DEVICES

All signs, sign holders, traffic cones, barricades or other work zone traffic control devices shall be in accordance with the National Cooperative Highway Research Program Report 350 Standards and approve by the SCDOT supplemental specifications released May 14, 2008. All traffic control signs shall be fabric, no rigid signs will be accepted. The City of Sumter reserves the right to reject any traffic control devices that are not SCDOT approved and to halt all construction until proper traffic control devices are installed. A list of all approved traffic control devices can be obtained from the City of Sumter's Engineering Department.

5A.3 PRECONSTRUCTION CONFERENCE

The contractor shall attend a preconstruction meeting on the project site with a representative of the SCDOT Sumter Maintenance Engineer s Office and a representative of the City Engineers Office prior to any construction beginning on SCDOT Right of Way. The contractor shall have in place all traffic control devices in accordance with the approved SCDOT Encroachment Permit prior to this meeting. The contractor shall request the preconstruction meeting a minimum of 24 hours in advance by contacting the City of Sumter's Engineering Department representative.